












Legend

Planting/Soft Landscaping

-  Heavy Standard Proposed Trees
-  Multi-Stemmed Trees
-  Existing trees to be retained
-  Planting Swathes Groundcover
-  Planting Swathes Perennial Shrub Mix
-  Planting Swathes Herbaceous Perennials, Herbs & Grasses
-  Riparian/Marginal Planting
-  Amenity Grass
-  Woodland Boundary Planting
-  Raingardens



Woodland Boundary Planting

Code	Species	Size (cm)	Density
Aff	<i>Athyrium filix-femina</i>	60-80	4pm2
Cs	<i>Cornus sanguinea</i>	80-100	2pm2
Ee	<i>Euonymus europaeus</i>	100-120	2pm2
Fa	<i>Frangula alnus</i>	100-120	2pm2
Lp	<i>Lonicera periclymenum</i>	100-120	2pm2
Ph	<i>Polygonatum x hybridum</i>	80-100	2pm2
Vc	<i>Viburnum opulus</i>	100-120	2pm2

Perennial Shrubs

Code	Species	Size (cm)	Density
AIV	<i>Artemisia ludoviciana 'Valerie Finnis'</i>	60-80	4pm2
Am	<i>Alchemilla mollis</i>	40-60	6pm2
Cn	<i>Chamaemelum nobile</i>	40-60	6pm2
EbM	<i>Erysimum 'Bowie's Mauve'</i>	60-80	4pm2
HsP	<i>Heuchera 'Sugar Plum'</i>	40-60	6pm2
Ms	<i>Malva sylvestris</i>	80-100	2pm2
SnL	<i>Salvia nemorosa 'Lubeca'</i>	40-60	6pm2

Riparian/Marginal Planting

Code	Species	Size (cm)	Grown
Ca	<i>Caltha palustris</i>	40-60	6pm2
Cp	<i>Carex pendula</i>	60-80	4pm2
Ip	<i>Iris pseudocarus</i>	80-100	2pm2
Ln	<i>Lysimachia nummularia</i>	40-60	6pm2
Ls	<i>Lythrum salicaria</i>	80-100	2pm2
MaA	<i>Melica altissima 'Alba'</i>	60-80	4pm2
Ma	<i>Mentha aquatica</i>	40-60	6pm2
Ms	<i>Myosotis scorpiodes</i>	40-60	6pm2
Pa	<i>Phragmites australis</i>	100-120	2pm2
Rf	<i>Ranunculus flammula</i>	40-60	6pm2

Groundcover Planting

Code	Species	Size (cm)	Density
Am	<i>Achillea millefolium</i>	40-60	6pm2
Ar	<i>Ajuga reptans</i>	40-60	6pm2
An	<i>Aneione nemosa</i>	40-60	6pm2
Bp	<i>Bellis perennis</i>	20-40	8pm2
Co	<i>Calendula officinalis</i>	40-60	6pm2
Ea	<i>Euphorbia amygdaloides</i>	40-60	6pm2
Go	<i>Galium odoratum</i>	40-60	6pm2
Oa	<i>Ophrys apifera</i>	40-60	6pm2
Pv	<i>Primula vulgaris</i>	20-40	8pm2

Herbaceous Perennials & Herbs Mix

Code	Species	Size (cm)	Density
AfC	<i>Achillea filipendulina 'Cloth of Gold'</i>	100-120	2pm2
As	<i>Allium schoenoprasum</i>	40-60	6pm2
Cp	<i>Campanula persicifolia</i>	80-100	4pm2
CvG	<i>Coreopsis verticillata 'Grandiflora'</i>	60-80	4pm2
DcB	<i>Deschampsia cespitosa 'Bronzeshleier'</i>	60-80	4pm2
Fv	<i>Filipendula vulgaris</i>	60-80	4pm2
Ih	<i>Inula hookeri</i>	60-80	4pm2
NfK	<i>Nepeta x faassenii 'Kit Cat'</i>	40-60	6pm2
Pc	<i>Petroselinum crispum</i>	40-60	6pm2
RpS	<i>Rodgersia pinnata 'Superba'</i>	80-100	4pm2
Rs	<i>Rumex sanguineus</i>	60-80	4pm2
Tp	<i>Tanacetum parthenium</i>	40-60	6pm2

Heavy Standard Trees

Code	Species	Size (cm)
Ag	<i>Ainus glutinosa</i>	150
Bp	<i>Betula pendula</i>	150
Bp (l)	<i>Betula pubescens</i>	150
Ca	<i>Corylus avellana</i>	120
Cr	<i>Quercus robur</i>	150
Sc	<i>Salix caprea</i>	120

NOTES:

Thoroughly cultivate all areas to be planted to a minimum depth of at least 300mm. Include during the cultivation mulching compost at a rate of 15litres per m2

Heavy and Extra Heavy Standard Trees to be planted into tree pits of 1200mm diameter 900mm and depth, each secured using a Platypus PF1 sub-surface root guying system and accessories. Backfill to be imported topsoil to BS3882, incorporating 80 litres of peat free compost thoroughly mixed into the backfill.

All shrubs to be planted in groups of 3, 5, 7 or 9 of the same species, each species evenly distributed throughout the planting bed. Each plant is to be planted in pits of 300mm diameter and depth, backfilled with imported topsoil to BS3882, incorporating 5 litres of peat free compost into each pit.

All areas to be grass seeded to be cultivated to a depth of at least 150mm, all debris and stones to be removed to contractors tip off site. The cultivation of these areas to be undertaken by machine, following the completion of any regrading works. Immediately prior to grass seeding carry out a final cultivation, and apply pre-seed fertiliser according to manufacturers recommendations.

Following the completion of planting, apply a 50mm layer of well rotted bark chippings.



Project	Rathfarnham Care Home Landscape Designs				
Title	Planting Plan 3 Southern Space				
Date	Scale	Drawn	Checked		
1.07.21	1:100 @ A1	KB	CS		
Job	Suitability	No.	Issue	Revision	
2045	PLANNING	L06	-	-	
LI WORKSTAGE:	0/1	2	3	4	5
	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

DISCLAIMER:  
Do not scale from this drawing.  
All dimensions to be verified on site prior to commencement of works.  
Drawing to be read in conjunction with related TGP drawings, consultants drawings and any other relevant information.  
This drawing is the copyright of TGP Landscape Architects Ltd. unless otherwise specified.