

SITE CHARACTERISATION REPORT

Ref: Danielle O'Kelly

Beechlawn Killakee

Rathfarnham

Dublin 16

DATE: 27 April 2022

Site Assessment Summary:

• Groundwater: Not Encountered at 2.1m

• Bedrock: Not Encountered at 2.1m

• Subsurface Value: 17

• Surface Value: N/A

• Well: >60m Upgradient

Based on the findings of the site assessment the following is recommended:

Recommended:

- 1. Install a 6PE Tricel (En & SR66 certified) sewage treatment plant
- 2. Install 5 X 10m long subsurface percolation trenches
- 3. Install a distribution box
- 4. Install vent pipes at the end of the trenches

Report & Recommendations prepared by: Waste Water Maintenance Ltd.

Site Pictures

Family Home, Site Views, Test location view & family business - Timber Trove / Sawmills









Site Pictures









SITE CHARACTERISATION FORM

COMPLETING THE FORM

Note: This form requires the latest version of Adobe Acrobat Reader

and on PC's Windows 7 or later. Windows XP produces errors

in calculations

Step 1:

Goto Menu Item File, Save As and save the file under a reference relating to the client or the planning application reference if available.

Clear Form

Use the Clear Form button to clear all information fields.

Notes:

All calculations in this form are automatic.

Where possible information is presented in the form of drop down selection lists to eliminate potential errors.

Variable elements are recorded by tick boxes. In all cases only one tick box should be activated.

All time record fields must be entered in twenty four hour format as follows: HH:MM

All date formats are DD-MM-YYYY.

All other data fields are in text entry format.

This form can be printed out fully populated for submission with related documents and for your files. It can also be submitted by email.

- Section 3.2 In this section use an underline _____ across all six columns to indicate the depth at which changes in classification / characteristics occur.
- Section 3.4 Lists supporting documentation required.
- Section 4 Select the treatment systems suitable for this site and the discharge route.
- Section 5 Indicate the system type that it is proposed to install.
- Section 6 Provide details, as required, on the proposed treatment system.

APPENDIX A: SITE CHARACTERISATION FORM

File Reference:
1.0 GENERAL DETAILS (From planning application)
Prefix: Ms First Name: Danielle Surname: O'Kelly
Address: Site Location and Townland:
Beechlawn, Killakee, Rathfarnham, Dublin 16 Same - proposed new house beside family home on the family land
Number of Bedrooms: 4 Maximum Number of Residents: 6
Comments on population equivalent
Proposed Water Supply: Mains Private Well/Borehole To be bored on-site Group Well/Borehole
2.0 GENERAL DETAILS (From planning application)
Soil Type, (Specify Type): Brown Podzolics / Acid Brown Earths
Subsoil, (Specify Type): Granite & metamorphic till
Bedrock Type: Granites & other Igneous Intrusive Rocks / Ordovician Metasediments
Aquifer Category: Regionally Important Locally Important L
Vulnerability: Extreme ✓ High Moderate Low
Groundwater Body: Kilcullen Status
Name of Public/Group Scheme Water Supply within 1 km:
Source Protection Area: ZOC SI SO Groundwater Protection Response:
Presence of Significant Sites (Archaeological, Natural & Historical): Massy's Estate Woods to the West & South
Past experience in the area: Areas of good soakage in often very sandy (granite) gravelly subsoils
Comments:
(Integrate the information above in order to comment on: the potential suitability of the site, potential targets at risk, and/or any potential site restrictions).
Ground water / aquifer are targets

Note: Only information available at the desk study stage should be used in this section.

3.0 ON-SITE ASSESSMENT

3.1 Visual Assessme	nt			
Landscape Position:	Hilly			
Slope:	Steep (>1:5)		Shallow (1:5-1:20) ✓	Relatively Flat (<1:20)
Slope Comment	-		Gradual slope W to E	
Surface Features within	n a minimum	of 250m (Dista	nce To Features Should Be Not	ed In Metres)
Houses:				
House to the SW >100m Family Home SE >80m (Houses N>200m		er inlaw)		
Existing Land Use:				
Existing family home & g	gardens with ag	gricultural fields to	the East	
Vegetation Indicators:				
No soakage indicators n	oted			
Groundwater Flow Dire	ection: We	st to East		
Ground Condition:				
Firm underfoot on test d	ays - dry sunny	weather on both	days	
Site Boundaries:				,
Hedging on the E & N si	des with wire fe	encing and open	fields.	

3.0 ON-SITE ASSESSMENT

3.1 Visual Assessment (contd.)

Roads:	
Killakee Road passes the driveway entrance to the house	
Outcrops (Bedrock And/Or Subsoil):	
None	
Surface Water Ponding:	
None on test days	
Lakes:	
None within 250m	
Beaches/Shellfish Areas:	
None within 250m	
Wetlands:	
None within 250m	
Karst Features:	
None	
Watercourses/Streams:*	
>150m to the south	

^{*}Note and record water level

3.0 ON-SITE ASSESSMENT

3.1 Visual Assessment (contd.) Drainage Ditches:* None Springs:* No springs noted Wells:* Well serving the family home upgradient >40m Comments: (Integrate the information above in order to comment on: the potential suitability of the site, potential targets at risk, the suitability of the site to treat the wastewater and the location of the proposed system within the site). The family home is served by a very old septic tank located in the rear SW corner of the garden and drains into a soak-pit. The system is over 40 years old and there are no recorded issues and no visible signs of any soakage issues. However it is proposed to install a modern waste water system directly behind the house >10m from the wall of the house.

^{*}Note and record water level

3.2 Trial Hole (should be a minimum of 2.1m deep (3m for regionally important aquifers))

To avoid any accidental damage, a trial hole assessment or percolation tests should not be undertaken in areas which are at or adjacent to significant sites, (e.g. NHAs, SACs, SPAs, and/or Archaeological etc.), without prior advice from National Parks and Wildlife Service or the Heritage Service.

Depth of trial I	nole (m): 2.1					
Depth from gr to bedrock (m			oth from grou vater table (m			
Depth of wate	r ingress:	Rock typ	e (if present): N	o rock or groundwate	r encountered a	t 2.1m
Date and time	of excavation: 2	2-Apr-2022	Date a	and time of examina	ation: 27-Apr-2	2022 09:30
Depth of Surface and	0.370					
Subsurface Percolation Tests	Soil/Subsoil Texture & Classification**	Plasticity and dilatancy***	Soil Structure	Density/ Compactness	Colour****	Preferential flowpaths
0.1 m 0.2 m 0.3 m 0.4 m	slightly sandy slightly gravelly SILT/CLAY 0-0.2m	Threads 5/3/3 Ribbons 85/60mm Dilates	Crumb	Firm	Brown	Rootlets
0.5 m	very sandy gravelly SILT with occasional cobbles 0.2-1.1m	Threads 4/3/1 Ribbons 50/30mm Dilates	Blocky	Firm / Soft	Brown	Random
1.1 m	sandy gravelly	Threads 5/3/2	Blocky	Firm / Soft	Brown	Random
1.6 m	SILT/CLAY with occasional cobbles & boulders 1.1-2.1m	Ribbons 70/60mm Dilates				
2.1 m	END OF PIT AT 2.1M					
2.6 m						
3.0 m 3.1 m 3.2 m 3.3 m 3.4 m 3.5 m						
100	face Percolation Version Value					

ote: *Depth of percolation test holes should be indicated on log above. (*Enter Surface or Subsurface at depths as appropriate).

^{**} See Appendix E for BS 5930 classification.

^{*** 3} samples to be tested for each horizon and results should be entered above for each horizon.


^{****} All signs of mottling should be recorded.

3.2 Trial Hole (contd.) Evaluation:

No seepage or mottling noted in the pit walls.
Groundwater is not a target

3.3(a) Subsurface Percolation Test for Subsoil

Step 1: Test Hole Preparation



Step 2: Pre-Soaking Test Holes

Pre-soak start	Date	26-Apr-2022	26-Apr-2022	26-Apr-2022
	Time	09:26	09:27	09:29
2nd pre-soak	Date	26-Apr-2022	26-Apr-2022	26-Apr-2022
start	Time	15:03	15:03	15:04

Each hole should be pre-soaked twice before the test is carried out.

Step 3: Measuring T₁₀₀

Percolation Test Hole No.	1	2	3
Date of test	27-04-2022	27-04-2022	27-04-2022
Time filled to 400 mm	09:31	09:32	09:32
Time water level at 300 mm	10:10	10:08	09:55
Time (min.) to drop 100 mm (T ₁₀₀)	39.00	36.00	23.00
Average T ₁₀₀			32.67

If $T_{100} > 480$ minutes then Subsurface Percolation value >120 – site unsuitable for discharge to ground

If $T_{100} \le 210$ minutes then go to Step 4;

If $T_{100} > 210$ minutes then go to Step 5;

Step 4: Standard Method (where $T_{100} \le 210$ minutes)

	1			2			3	
Start Time (at 300 mm)	Finish Time (at 200 mm)	∆t (min)	Start Time (at 300 mm)	Finish Time (at 200 mm)	Δt (min)	Start Time (at 300 mm)	Finish Time (at 200 mm)	Δt (min)
10:10	10:56	46.00	10:08	10:43	35.00	09:55	10:49	54.00
10:56	12:04	68.00	10:43	11:38	55.00	10:49	12:15	86.00
12:04	13:28	84.00	11:38	12:55	77.00	12:15	14:04	109.00
		66.00			55.67		,	83.00
Average ∆t [Hole No.1]	-	16.50 (t,)	Average ∆t	0	13.92 (t ₂)	Average Δ		20.75 (t ₃)
	Time (at 300 mm) 10:10 10:56 12:04 Average Δt	Start Finish Time Time (at 300 (at 200 mm)) 10:10 10:56 10:56 12:04 12:04 13:28 Average Δt/4 =	Start Finish Δt (min) Time Time (at 300 (at 200 mm)) 10:10 10:56 46.00 10:56 12:04 68.00 12:04 13:28 84.00 66.00 Average Δt/4 =	Start Finish Time Δt (min) Start Time (at 300 mm) 10:10 10:56 46.00 10:08 10:56 12:04 68.00 10:43 12:04 13:28 84.00 11:38 66.00 Average Δt/4 = Average Δt	Start Finish Δt (min) Start Finish Time Time (at 300 (at 200 mm)) mm) Start Finish Time (at 300 mm) (at 200 mm) mm) 10:10 10:56 46.00 10:08 10:43 11:38 12:04 13:28 84.00 11:38 12:55 66.00 Average $\Delta t/4 =$	Start Finish Δt (min) Time Time (at 300 (at 200 mm)) Finish Δt (min) Time Time (at 300 (at 200 mm)) Time (at 300 (a	Start Finish Time Time (at 300 mm) Δt (min) Time (at 300 mm) Start Time Time (at 300 mm) Time (at 300 mm) Start Time Time (at 300 mm) Start Time (at 300 mm) In 300 mm Start Time (at 300 mm) In 300 mm In 300 mm <td>Start Finish Time Time (at 300 (at 200 mm)) Start Finish Time Time (at 300 (at 200 mm)) Start Finish Time Time (at 300 (at 200 mm)) Start Finish Time Time (at 300 (at 200 mm)) Time Time Time Time (at 300 (at 200 mm)) Time Time Time (at 300 (at 200 mm) Time Time Time Time (at 300 mm) Time Time Time Time Time Time Time Time</td>	Start Finish Time Time (at 300 (at 200 mm)) Start Finish Time Time (at 300 (at 200 mm)) Start Finish Time Time (at 300 (at 200 mm)) Start Finish Time Time (at 300 (at 200 mm)) Time Time Time Time (at 300 (at 200 mm)) Time Time Time (at 300 (at 200 mm) Time Time Time Time (at 300 mm) Time Time Time Time Time Time Time Time

Comments:

The subsoil in the tested area is considered suitable for the treatment of effluent

Step 5: Modified Method (where $T_{100} > 210$ minutes)

Percolation Test Hole No.		1				
Fall of water in hole (mm)	Time Factor = T,	Start Time hh:mm	Finish Time hh:mm	Time of fall (mins) = T _m	K _{ts} = T, / T _m	T – Value = 4.45 / K _{fs}
300 - 250	8.1			0.00		
250 - 200	9.7			0.00		
200 - 150	11.9			0.00		
150 - 100	14.1			0.00		
Average	T- Value	e	T- Valu	e Hole 1	= (T ₁)	0.00

Percolation Test Hole No.		3				
Fall of water in hole (mm)	Time Factor = T,	Start Time hh:mm	Finish Tim§e hh:mm	Time of fall (mins) = T _m	K _{ts} = T, / T _m	T – Value = 4.45 / K _{fs}
300 - 250	8.1			0.00		
250 - 200	9.7			0.00		
200 - 150	11.9			0.00		
150 - 100	14.1			0.00		

Percolation Test Hole No.		2				
Fall of water in hole (mm)	Time Factor = T,	Start Finish Time Time hh:mm hh:mm		Time of fall (mins) = T _m	K _{ts} = T _f / T _m	T – Value = 4.45 / K _{fs}
300 - 250	8.1			0.00		
250 - 200	9.7			0.00		
200 - 150	11.9			0.00		
150 - 100	14.1			0.00		


Result of Test: Subsurface Percolation Value =

0.00 (min/25 mm)


Comments:

3.3(b) Surface Percolation Test for Soil

Step 1: Test Hole Preparation



Each hole should be pre-soaked twice before the test is carried out.



If $T_{100} > 480$ minutes then Surface Percolation value >90 – site unsuitable for discharge to ground

If $T_{100} \le 210$ minutes then go to Step 4;

If T₁₀₀ > 210 minutes then go to Step 5;

Step 4: Standard Method (where $T_{100} \le 210$ minutes)

Percolation Test Hole			1				2				3		
Fill no.	Start Time (at 30 mm)	0 (Finish Fime at 200 mm)	ΔT (r	nin)	Start Time (at 300 mm)	Finish Time (at 200 mm)	ΔT (min)	Star Tim (at 3 mm)	e 00	Finish Time (at 200 mm)	ΔΤ	(min)
1					0.00			0.00					0.00
2					0.00			0.00					0.00
3					0.00			0.00					0.00
Average ∆T Value					0.00			0.00					0.00
Result of Te	[Hole				0 (T ₁)	Average / [Hole No.	2]	0.00 (T ₂) [Hole	age ∆T/ e No.3]		0.0	00 (T ₃)
Step 5: Mo Percolation Test Hole No.	amea k	1	(where	1100 > 2	. 10 11111	nutes)	Percolation Test Hole No		2				
Fall of water in hole (mm)	Time Factor = T,	Start Time hh:mm	Finish Time hh:mm	Time of fall (mins) = T _m	K _{ts} = T _r / T _m	T – Value = 4.45 / K _{fs}	Fall of wate in hole (mm		Start Time hh:mm	Finish Time hh:mm	Time of fall (mins) = T _m	K _{fs} = T, / T _m	T – Value = 4.45 / K _{fs}
300 - 250	8.1			0.00			300 - 250	8.1			0.00		
250 - 200	9.7			0.00			250 - 200	9.7			0.00		
200 - 150	11.9			0.00			200 - 150	11.9			0.00		
150 - 100	14.1			0.00			150 - 100	14.1			0.00		
Average	T- Value	е	T- Valu	e Hole 1	= (T ₁)	0.00	Average	T- Valu	ie	T- Valu	ue Hole 2	! = (T ₂)	0.00
							Result of	of Test: S	urface I	Percola	tion Val	ue =	
Percolation Test Hole No.		3							(0.00	(min/25	mm)	
Fall of water in hole (mm)	Time Factor = T,	Start Time hh:mm	Finish Time hh:mm	Time of fall (mins) = T _m	K _{fs} = T ₁ / T _m	T – Value = 4.45 / K _{ts}	Comment	s:					
300 - 250	8.1			0.00									
250 - 200	9.7			0.00									
200 - 150	11.9			0.00									
150 - 100	14.1			0.00									
			William										
Average	T- Value	е	T- Valu	e Hole 3	$= (T_2)$	0.00							

3.4 The following associated Maps, Drawings and Photographs should be appended to this site characterisation form.

- 1. Discovery Series 1:50,000 Map indicating overall drainage, groundwater flow direction and housing density in the area.
- Supporting maps for vulnerability, aquifer classification, soil, subsoil, bedrock.
- North point should always be included.
- 4. (a) Scaled sketch of site showing measurements to Trial Hole location and
 - (b) Percolation Test Hole locations,
 - (c) wells and
 - (d) direction of groundwater flow (if known),
 - (e) proposed house (incl. distances from boundaries)
 - (f) adjacent houses,
 - (g) watercourses,
 - (h) significant sites
 - (i) and other relevant features.
- Site specific cross sectional drawing of the site and the proposed layout¹ should be submitted.
- 6. Photographs of the trial hole, test holes and site including landmarks (date and time referenced).
- 7. Pumped design must be designed by a suitably qualified person.

¹ The calculated percolation area or polishing filter area should be set out accurately on the site layout drawing in accordance with the code of practice's requirements.

4.0 CONCLUSION of SITE CHARACTERISATION

Integrate the information from the desk study and on-site assessment (i.e. visual assessment, trial hole and percolation tests) above and conclude the type of system(s) that is (are) appropriate. This information is also used to choose the optimum final disposal route of the treated wastewater. Slope of proposed infiltration / treatment area: 1:200 Are all minimum separation distances met? Depth of unsaturated soil and/or subsoil beneath invert of gravel 0.90 (or drip tubing in the case of drip dispersal system) Sub-surface: 17.00 Percolation test result: Surface: Suitable for Development Not Suitable for Development Discharge Route 1 Identify all suitable options Septic tank system (septic tank and No Proposed to install a sewage treatment plant and percolation area) (Chapter 7) subsurface trench soil polishing filter with a final discharge to ground water. Secondary Treatment System 2. Yes (Chapters 8 and 9) and soil polishing filter (Section 10.1) Tertiary Treatment System and Infiltration / Yes treatment area (Section 10.2) **5.0 SELECTED DWWTS** Propose to install: Secondary Treatment System and soil polishing filter and discharge to: Ground Water Invert level of the trench/bed gravel or drip tubing (m) 0.70 Site Specific Conditions (e.g. special works, site improvement works testing etc. Based on the site assessment the site is considered suitable for an on-site sewage system. It is proposed to install a new sewage treatment plant in conjunction with a constructed subsurface trench soil polishing filter subject to approval by the County Council. The system must be installed in accordance with the EPA CoP 2021. Only foul and grey water to discharge to the sewage system. Storm water must not be allowed into the sewage system.

A discharge of sewage effluent to "waters" (definition includes any or any part of any river, stream, lake, canal, reservoir, aquifer, pond, watercourse or other inland waters, whether natural or artificial) will require a licence under the Water Pollution Acts 1977-90. Refer to Section 2.4.

6.0 TREATMENT SYSTEM DETAILS

Tank Capacity (m³)		Percolation Area		Mounded Percolation Area	
		No. of Trenches		No. of Trenches	
		Length of Trenches (m)		Length of Trenches (m)	
		Invert Level (m)	Invert Level (m)		
SYSTEM TYPE: Seco	ndary Treatn	nent System (Chapter	s 8 and 9) and	polishing filter (Section 10.1)	
Secondary Treatment Systems receiving septic tank effluent (Chapter 8)				Packaged Secondary Treatment Systems receiving raw wastewater (Chapter 9)	
Media Type	Area (m²)*	Depth of Filter	Invert Level	Туре	
Sand/Soil				Tricel Treatment Plant	
Soil				Capacity PE 6	
Constructed Wetland				Sizing of Primary Compartmen	
Other				m³	
Polishing Filter*: (Se Surface Area (m²)*	ection 10.1)			Gravity Discharge 50.00	
Option 1 - Direct Disc	harge		Option 4 - I	ow Pressure	
Surface area (m²)			Pipe Distrib	ution	
Option 2 - Pumped Di Surface area (m²)	scharge		Trench leng		
		Option 5 - Drip Surface area (m			
SYSTEM TYPE: Tertia	ary Treatmen	t System and infiltrat	ion / treatment	t area (Section 10.2)	
Identify purpose of tertiary treatment		Provide performand demonstrating system required treatment	em will provide	Provide design information	
		Tricel STP En & SR6 BOD 95.9 SS 95.3 NH4-N 74.9	6 Certified	Sewage Treatment Plant and a subsurface trench soil polishing filter with final discharge to ground water	
DISCHARGE ROUTE:				;	
Groundwater	Hydraulic	Loading Rate * (I/m².d)	900.00	Surface area (m²)	
Surface Water **	Discharge	Rate (m³/hr)	0.04		

^{*} Hydraulic loading rate is determined by the percolation rate of subsoil

^{**} Water Pollution Act discharge licence required


6.0 TREATMENT SYSTEM DETAILS

QUALITY ASSURANCE:

Installation & Commissioning
The installation must be supervised by suitably qualified person with a Completion Report prepared to include photographic evidence on completion of works.
On-going Maintenance
The system must be desludged annual or in accordance with the manufacturers instructions and serviced at least once every year by a suitably qualified person.
×
7.0 SITE ASSESSOR DETAILS
Company: Waste Water Maintenance Limited
Prefix: Mr First Name: Aidan Surname: Comerford
Address: 149 Woodfield, Scholarstown Road, Rathfarnham, Dublin 16
Qualifications/Experience: EPA SIte Assessor, Dip. Environmental Impact & Strategic Impact Assessment
Data of Danasta (07 Apr. 2002)
Date of Report: 27-Apr-2022
Phone: E-mail info@wastewater.ie
Indemnity Insurance Number: ARB PI/D/1256/20/1
NC 1 -
Signature:




Vulnerability Extreme



Scale: 1:50,000

Geological Survey Ireland





١

This map and its data may not be used or reproduced for commercial purposes without the prior written permission of Copyright holders. This map is a user generated static output from an Internet mapping site and is for general reference only.

Data layers that appear on this map may or may not be accurate, current, or otherwise reliable.

Map Centre Coordinates (ITM) 712,072 724,019 4/27/2022, 4:21:10 PM

Ordnance Survey Ireland Licence No. EN 0047221 © Ordnance Survey Ireland/Government of Ireland © Geological Survey Ireland/Government of Ireland

Legend

Groundwater_Vulnerability_40K_IE...

Rock at or near Surface or Karst

Extreme

High

Moderate

Low

Water



Aquifer Locally Important




Scale: 1:50,000

Geological Survey Ireland

This map is a user generated static output from an Internet mapping site and is for general reference only.

Data layers that appear on this map may or may not be accurate, current, or otherwise reliable.



Map Centre Coordinates (ITM) 712,072 724,019 4/27/2022, 4:26:27 PM

Ordnance Survey Ireland Licence No. EN 0047221 © Ordnance Survey Ireland/Government of Ireland @ Geological Survey Ireland/Government of Ireland

Legend


— Bedrock Aquifer Faults

Bedrock Aquifer

- LI Locally Important Aquifer Bedrock which is Moderately Productive only in Local
- PI Poor Aquifer Bedrock which is Generally Unproductive except for Local



Bedrock GII / OM



Scale: 1:50,000

Geological Survey Ireland

Data layers that appear on this map may or may not be accurate, current, or otherwise reliable



Map Centre Coordinates (ITM) 712,072 724,019 4/27/2022, 4:34:27 PM

Ordnance Survey Ireland Licence No. EN 0047221 © Ordnance Survey Ireland/Government of Ireland @ Geological Survey Ireland/Government of Ireland

Legend

Groundwater Rock Units

- Dinantian Upper Impure Limestones
- Granites & other Igneous Intrusive rocks
- Ordovician Metasediments