

PAVILION DESIGN

DUE TO DESIGN


DEVELOPMENT

LAYOUT CHANGES

ALL DIMENSIONS TO BE CHECKED ON SITE

NO DIMENSIONS TO BE SCALED FROM THIS DRAWING

DRAWING IS TO BE READ IN CONJUNCTION WITH RELEVANT CONSULTANTS DRAWINGS



NON RFI RELATED CHANGES



GENERAL NOTES:

ALL INTERNAL APARTMENT LAYOUTS HAVE BEEN AMENDED DUE TO DESIGN DEVELOPMENT AND CO-ORDINATION WITH OTHER DISCIPLINES. THE INDIVIDUAL UNITS MAINTAIN THE SPACE REQUIREMENT CUIDELINES AS PER THE ORIGINAL PLANNING SUBMISSION

MINOR AMENDMENTS TO M&E AND SE LAYOUTS DUE TO DESIGN DEVELOPMENT & TO ACCOMMODATE COMPLIANCE WITH STATUTORY REQUIREMENTS

REDUCED PARAPET HEIGHT & FALL ARREST SYSTEM INTRODUCED TO BLOCKS A,C,D AND RESIDENT PAVILLION BUILDINGS DUE TO MAINTENANCE. PARAPET HEIGHT OF TOWER ELEMENT OF BLOCK C1 RETAINED AS PER ORIGINAL PLANNING APPLICATION

RFI1(a)

Block D North - Changes to Core entrance hall facing Great Western Way updated to accommodate new apartment type T.301_D revised apartment type T.102_D

RFI1(b)

Block D South - Changes to apartment type T.201_D and T.202_D to overcome privacy/overlooking issues

RFI2

Block D South - Changes to facade material to brick on the upper floor levels



Red dash line indicates extent of amendments to address RFI 0723 dated 08 JUNE 2022

HJL Drawing Number on previously lodged planning application: SDZ22A/0005

ADC3-HJL-ACD-ZZ-DR-A-P2020 Revision (P01)

ELEVATION MATERIAL LEGEND

BE 01 - METALIC BALCONY SCREEN WITH PPC FINISH **BL 01** - BALCONY SYSTEM WITH PPC METAL RAILING

BL 02 - BALCONY SYSTEM WITH GLAZED BALUSTRADE

BL 03 - SELECTED RAINSCREEN CLADDING

BR 01 - SELECTED LIGHT RED COLOURED BRICK

BR 02 - SELECTED DARK RED COLOURED BRICK BR 03 - SELECTED LIGHT GREY COLOURED BRICK

BR 04 - SELECTED GLAZED BRICK

BR 05 - ARCHITECTURAL BRICK FEATURE

CL 01 - RAINSCREEN CLADDING

CP 01 - PRESSED ALUMINIUM CAPPING WITH PPC FINISH

CW 01 - SELECTED CURTAIN WALL GLAZING SYSTEM DR 01 - SELECTED GLAZED ENTRANCE DOOR AND SIGNAGE

DR 02 - METAL DOOR WITH PPC FINISH

ES 01 - ESB DOORS

GA 01 - GLAZED ENTRANCE GATE

GL 01 - SELECTED DOUBLE GLAZED WINDOW SYSTEM MS 01 - SELECTED MESH SCREENING

RE 01 - LIGHT EXTERNAL INSULATED RENDER FINISH

RE 02 - LIGHT RED EXTERNAL RENDER FINISH RE 03 - DARK EXTERNAL INSULATED RENDER FINISH

RL 01 - PPC METAL ENCLOSURE TO BICYCLE STORE

RL 02 - PPC METAL GATE


RL 03 - PPC METAL RAILINGS

AB 01 - AIRBRICK

CA 01 - FAIRFACED RC CANOPY

PS 01 - PERFORATED METAL SCREEN GATES

RP 01 - RAIN WATER PIPES SG 01 - SHADOW GAP IN RENDERED FINISH



STATUS CODE DESCRIPTION

SUITABLE FOR INFORMATION

CLIENT

QUINTAIN IRELAND LTD.

PROJECT

ADAMSTOWN STATION BLOCKS ACD

DRAWING

RESIDENT'S PAVILLION ELEVATIONS

PROJECT NUMBER DATE 950747 08/04/22 SCALE@ A1: DRAWN/CHECKED: As indicated FM/RJ STATUS CODE: DRAWING NUMBER REVISION ADC3-HJL-ACD-ZZ-DR-A-P2020

Henry J Lyons

info@henryjlyons.com

Dublin D02 KA66