LEGEND

Application Boundary (See Architects' Site Layout Plan for full extent)

Building Accecss

SOFT LANDSCAPE

Proposed Boundary Buffer Tree Planting - 39 no.
Standard single stem tree
Species: *Carpinus betulus, Tilia cordata, Quercus robur 'Fastigiata'*

Proposed Street Tree Planting - 68 no.
Standard single stem tree
Species: *Quercus robur Regal Prince'* (public), *Alnus glutinosa' Imperialis'* (internal)

Proposed Native Woodland Tree Planting - 234 no.
Native tree; Multi-stem/Feathered/Bush Forms
Species: *Betula pendula, Alnus glutinosa, Populus tremula, Crategus monogyna, Pinus sylvestris, Ilex aquifolium, Corylus avellana*

Proposed Tree Planting - 133 no., to open space area
Multi-stem trees, Native
Species: *Populus tremula, Betula pendula, Arbutus unedo, Ilex aquifolium, Betula pendula*

Proposed Shrub & Hedge Planting - Boundary buffer area 673.41 m²
Mixed native species
Species: *Crategus monogyna, Ilex aquifolium, Corylus avellana, Cornus sp., Viburnum opulus; Prunus spinosa, Salix caprea, Salix aurita, Rosa canina, Lonicera periclymenum*

Proposed Hedge Planting - Along street & building 677.81 m²
1.8m ht. Evergreen
Species: *Ilex aquifolium, Taxus baccata, Fagus sylvatica*

Proposed Wetland (Bio-retention) Planting 3164.19 m²
Native shrub mix with wild flower / perennial ground layer
Shrub Species: *Salix caprea, Salix purpurea, Salix aurita, Corylus avellana, Cornus sp., Prunus spinosa*

Proposed Wetland (Bio-retention) Planting 1203.62 m²
Native Wildflower Mix - Seasonally Flood Mix EC05 by Design by Nature or similar

Shrub & Ornamental Grass Planting - Street area at site boundary 877.09 m²
Structurted bands of groundcover shrubs 0.5-1.5m ht. - See sections
1878_PL_S_01/02/03/04
Native hedge species, as above with street tree *Quercus robur* 'Regal Prince'

Rain Garden Planting - Plaza area 355.80 m²
Wildflower mix

Grass Verge - Grass lawn along road 1813.33 m²

Grasscrete - to fire access area 1218.99 m²
Seeded with native wildflower meadow

Wildflower Meadow- Open space wildflower 4022.79 m²
To be selected with Ecologist's input

Green Roof Planting - wildflower and low shrubs 1235.30 m²
Species: *Rosa canina, Rosa pimpinellifolia, Viburnum opulus, Lonicera periclymenum*
SuDS Details as per 1878_PL_D_03

Living Wall - to Unit 6 building facade
Diverse native climbers, ferns, grasses, perennials

Bio-retention Area
SuDS Details as per 1878_PL_D_03
Planting to include Native Wildflower Seed Mix EC05 as above with container-grown aquatic perennials and grasses such as: *Caltha palustris, Glyceria maxima, Deocampsia cespitosa, Iriah pseudacorus, Juncus effusus*, etc.

1. The drawing is intended to show landscape architectural proposals only. Please refer to Architects and Engineer's drawings for relevant details of buildings, structures, roads, parking, etc.
2. The copyright of this drawing is vested with Murray & Associates. This drawing may not be copied or reproduced without written consent.
3. All materials referred to on this drawing - including plant species - are indicative and subject to availability. Alternatives will be considered, significant changes, if any are required, will be referred to the relevant authority for agreement.
4. This drawing is not suitable for use for construction purposes.
5. Discrepancies to be referred to Murray & Associates for clarification.

murray & associates
landscape architecture

15 The Seaport Building,
Dublin Port,
Dublin 3, D03 P8N3

mail@murray-associates.com
www.murray-associates.com
+353 (0)1 854 0890

REV	DATE	REVISION	DRAWN	CHECKED
0	01/04/22	Planning Issue	HT	MB

CLIENT
Blackwin Limited

PROJECT TITLE
Warehousing / Logistics and Office Development at Calmount Road

SHEET TITLE
Soft Landscape Plan and Details

SHEET NO.	SHEET SIZE
1878_PL_P_01	A0
SCALE	**REVISION**
As Shown	0
STAGE	**DATE**
PLANNING	01/04/22

Copyright Murray and Associates, 2022