



Car Park

OLD NAAS ROAD

EX: 6000 CONCRETE FS
OLD NAAS ROAD

EX: 6000 CONCRETE FS

SO05284901
CL: 91.37
IL: 89.27

SO05284801
CL: 93.17
IL: 90.87

NOTE:
MANHOLES TO RECEIVE 150mm CONCRETE SURROUND.
CONTRACTOR TO CARRY OUT AIR TEST AND CCTV OF PRIVATE SIDE DRAINAGE AROUND HOUSE TO PROVE INTEGRITY BEFORE COMPLETION OF UNITS.

KEY PLAN.
SCALE= 1:2000

PHASING PLAN FOR SUDS IMPLEMENTATION.
SCALE= 1:2000

NOTE:
ALL INSPECTION CHAMBERS TO COMPLY WITH PART H OF THE BUILDING REGULATIONS. REFER TO BELOW FOR DEPTHS AND INSPECTION CHAMBER DIAMETER.
DEPTH TO INVERT < OR = 600mm ALLOW FOR 450mm DIAMETER CHAMBER.
DEPTH TO INVERT 600mm - 900mm ALLOW FOR 600mm DIAMETER CHAMBER.
DEPTH TO INVERT 900mm - 1200mm ALLOW FOR 900mm DIAMETER CHAMBER

PIPE MATERIALS
ALL FOUL SEWER PIPE MATERIALS SHALL BE PVC SDR OR IN COMPLIANCE WITH SECTION 3.13 OF THE IRISH WATER CODE OF PRACTICE FOR WASTEWATER.
PROPOSED SW SEWERS UP TO 300mm IN DIAMETER TO BE UPVC ABOVE 300mm IN DIAMETER TO BE CONCRETE IS EN 1916(2002).

LEGEND

- SITE BOUNDARY
- EXISTING FOUL WATER SEWER AND MANHOLE
- PROPOSED FOUL WATER SEWER AND MANHOLE
- PROPOSED FOUL WATER INSPECTION CHAMBER
- PROPOSED STORM WATER SEWER AND MANHOLE
- PROPOSED STORM WATER INSPECTION CHAMBER
- PROPOSED STORM WATER CATCHPIT AND MANHOLE. REFER TO G104-CSC-ZZ-XX-DR-C-0018
- PROPOSED LAND DRAIN WITH COLLECTION AJ
- PROPOSED 100mm uPVC PERFORATED DRAIN SET 100mm ABOVE BASE OF PERMEABLE PAVING
- PROPOSED PERMEABLE PAVING
- PROPOSED INTEGRATED TREE PIT
- PROPOSED ATTENUATION TANK
- PROPOSED BIO-RETENTION AREA
- PROPOSED INFILTRATION TRENCH
- PROPOSED INFILTRATION TRENCH IN REAR GARDEN WITH 150mm uPVC PERFORATED PIPE SET OFF BASE WRAPPED IN GEOTEXTILE
- OVERFLOW INSPECTION CHAMBER FROM TREE PITS AND BIO RETENTION AREA TO MAIN SW SEWER
- SW AJ TO RECEIVE WATER FROM RWPS FROM FRONT HALF OF ROOFS AND DISCHARGE TO PERMEABLE PAVING
- KERB INLET GULLY TO BIO RETENTION AREA
- TRADITIONAL PRECAST ROAD GULLY

- NOTES:**
- THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS.
 - ALL LEVELS ARE IN METRES O.D. MALIN HEAD.
 - THE POSITION AND LEVELS OF EXISTING SERVICES INsofar AS THEY ARE KNOWN AND AS SHOWN ON THE DRAWINGS MAY NOT BE ACCURATE AND MERELY INDICATE THEIR PRESENCE IN THE WORKING AREA. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING EXISTING SERVICES ON SITE.
 - THE SURVEY INFORMATION SHOWN ON THIS DRAWING IS TAKEN FROM A TOPOGRAPHICAL SURVEY UNDERTAKEN BY MURPHY GEOSPATIAL IN MAY 2021, DRAWING REFERENCE MGR41690_TJM_Rev2.
 - FOR DETAILS OF LONGITUDINAL SECTIONS REFER TO DRG. No. G104-CSC-ZZ-XX-DR-C-0010.
 - FOR DETAILS OF BEDDING REFER TO DRG. No. G104-CSC-ZZ-XX-DR-C-0015.
 - FOR DETAILS OF BUILDING DRAINAGE CONNECTIONS REFER TO ARCHITECTS AND M+E DRAWINGS
 - ALL PIPEWORK IS 150mm UNLESS OTHERWISE NOTED.
 - WHERE EXCAVATIONS FOR DRAINAGE ENCOACH ON THE BEARING FOR FOUNDATIONS (IE. PIPE IS BELOW FOUNDATION OR BELOW 45° LINE EXTENDING OUT AND DOWN FROM THE BOTTOM OF THE FOUNDATION), SUCH EXCAVATIONS SHALL BE BACKFILLED IN LEAN MIX CONCRETE TO FORMATION LEVEL OF FOUNDATIONS. NEW FOUNDATIONS WILL BE INSTALLED AT A DEPTH TO SLIT THE PROPOSED NEW DRAINAGE.
 - PIPE BEDDING AND BACKFILL SHALL BE AS PER DRAWING G104-CSC-ZZ-XX-DR-C-0015 WITH CLASS B BEDDING FOR FLEXIBLE PIPE (uPVC AND THERMOPLASTIC STRUCTURED WALL PIPE) AND CLASS B BEDDING FOR RIGID PIPE (CONCRETE). BACKFILLING OF TRENCHES ABOVE PIPE BED AND SURROUND SHALL BE AS PER NOTE 10 ABOVE. WHERE TRENCHES ARE BENEATH SLABS AND CONCRETE SURFACES, THE TRENCHES SHALL BE BACKFILLED WITH HARDCORE COMPLYING WITH THE REQUIREMENTS OF SR21 AND IS EN 13242.
 - SURFACE WATER SEWERS WITH A DIAMETER OF 150mm AND 225mm SHALL BE uPVC. ALL SURFACE WATER SEWERS WITH A DIAMETER OF 300mm AND GREATER SHALL BE CONCRETE PIPES UNLESS NOTED OTHERWISE. REFER TO LONG SECTIONS FOR SPECIFIED PIPE MATERIAL.
 - WHERE AN UNDERGROUND PIPE IS BUILT INTO A STRUCTURE THERE SHALL BE TWO FLEXIBLE JOINTS ADJACENT TO THE STRUCTURE. THE FIRST SHALL NOT BE MORE THAN ONE PIPE DIAMETER FROM THE OUTSIDE FACE OF THE STRUCTURE. THE LENGTH OF THE NEXT PIPE (ROCKER PIPE) SHALL NOT EXCEED 750mm FOR PIPES UP TO 450.
 - SETTING OUT OF ALL SVP'S AND RWP'S TO ARCHITECTS DETAILS.
 - DRAINAGE TO LANDSCAPED AND NON CARRIAGEWAY PAVED AREAS BY LANDSCAPE ARCHITECTS.
 - ALL MANHOLES TO BE SET OUT ON SITE AND CO-ORDINATED WITH PROPOSED AND EXISTING SERVICES PRIOR TO CONSTRUCTION.
 - COVER LEVEL TO BE CO-ORDINATED WITH PROPOSED LANDSCAPING LEVELS.
 - ALL MANHOLE COVERS IN TRAFFICKED AREAS TO BE A MINIMUM OF CLASS D400 SOLID TOP COVERS. RECESSED COVERS TO BE PROVIDED IN PAVED LANDSCAPED AREAS.

PROPOSED DRAINAGE
SCALE 1:250

CONNECTION TO EXISTING PUBLIC NETWORK BY IRISH WATER CONTRACTOR

COMPLIANCE
SD21A/0327

- NOTES**
- For setting out refer to Architect's drawings.
 - This drawing to be read in conjunction with all other Architectural and Engineering drawings and all other relevant drawings and Specifications.
 - DO NOT SCALE THIS DRAWING. Use figured dimensions only.
 - No part of this document may be reproduced or transmitted in any form or stored in any retrieval system of any nature without the written permission as copyright holder except as agreed with the client for use on the project for which the document was originally issued.
 - Ordnance Survey Ireland Licence Number EN 0074022

Rev. No.	Date	REVISION NOTE	Dim. by	Chkd. by
1	16.08.2022	DRAFT COMPLIANCE ISSUE	SC	NB
2	18.08.2022	ISSUED FOR COMPLIANCE	SC	NB
3	08.09.2022	ISSUED FOR COMPLIANCE	SC	NB
4	12.09.2022	ATTENUATION TANK SIZE UPDATED	SC	NB

Client: GREENWALK DEVELOPMENTS LTD
Project: PROPOSED RESIDENTIAL DEVELOPMENT AT GORDON PARK
Title: Proposed Drainage for Compliance Sheet 1 of 2
Dwg. No: G104-CSC-ZZ-XX-DR-C-0022
Date: AUG 2022
Dim by: SC
Chkd by: FDB
Appr'd by: NB
Scale: 1:250 @ A1
Revision: C3

CS Consulting Group
DUBLIN | LONDON | LIMERICK
Head Office
19-22 Dame Street, Dublin 2.
T: +353 (0)1 5480883
E: info@csconsulting.ie
W: www.csconsulting.ie
Quality
Environment
Energy
Health & Safety
I.S. EN ISO 9001:2008
I.S. EN ISO 14001:2004
I.S. EN ISO 50001:2011
OHSAS 18001:2007