



Plant schedule, to include the following but not limited to:

- Trees:**
- Acer platanoides 'Columnare', r/b, 20-25cm girth
 - Acer platanoides 'Drummondii', r/b, 20-25cm girth
 - Amelanchier lamarkii, r/b, multistem, 3.0-3.5m tall
 - Betula pubescens, r/b, 20-25cm girth
 - Betula utilis 'Jaquemontii', r/b, multistem 4.0-4.5m tall
 - Cercis canadensis 'Forest Pansy', r/b, 16-18cm girth, 4.0-4.5m tall
 - Fagus sylvatica 'Dawson's Purple', r/b, 18-20cm girth, clear stem to 2.0m
 - Fagus sylvatica 'Dawson's Gold', r/b, 3.5-4.0m tall (feathered)
 - Liquidambar styraciflua, r/b, 18-20cm girth
 - Prunus padus, r/b, 18-20cm girth
 - Pyrus 'Chanticleer', r/b, 18-20cm girth
 - Tilia platyphyllos, r/b 30-35cm girth
- Woodland Mix:**
- Acer campestre
 - Alnus glutinosa
 - Betula pubescens
 - Crataegus monogyna
 - Larix decidua
 - Pinus sylvestris
 - Quercus rubra
 - Carex pendula
 - Digitalis purpurea
 - Narcissus 'White Marble'
 - Camassia caerulea
- Native hedgerow infill planting, planted at 5/linear meter:**
- Corylus avellana, Hazel
 - Crataegus monogyna, Hawthorn
 - Euonymus europaeus, Spindle
 - Ilex aquifolium, Holly
 - Prunus spinosa, Blackthorn

- Hedging:**
- Carpinus betulus - double staggered row: 5/linear meter
 - Prunus lusitana 'Augustifolia', r/b, 800-1000mm tall. (3 per linear m)

- Shrubs / Perennials:**
- Anemone 'Honorine Jobert', c/f, 2L
 - Ceanothus thyrsiflorus repens, c/f, 2L (3/Sq.m.)
 - Crocus 'Lucifer', c/f, 2L (7/Sq.m.)
 - Hebebeon orientalis c/f, 2L (5/Sq.m.)
 - Hydrangea 'Lime light', c/f, (3/Sq.m.)
 - Hypericum hidcote, c/f, (3/Sq.m.)
 - Miscanthus sinensis 'Fern Osten', c/f, 2L (4/Sq.m.)
 - Pachysandra terminalis, c/f, 2L
 - Perovskia 'Blue Spire', c/f, 2L (plant 3/lin. M)
 - Prunus 'Otto Luyken', c/f, 2L, (plant 3/lin. M)
 - Rudbeckia fulgida 'Goldsturm', c/f, 2L (4/Sq.m.)
 - Sarcococca confusa, c/f, 2L (plant 3/lin. M)
 - Stipa gigantea, c/f, (3/Sq.m.)
 - Verbena bonariensis, c/f, (3/Sq.m.)

- Bulbs:**
- Allium hollandicum 'Purple Sensation' @ 10/Sq.m.
 - Leucolium aestivum (bulbs at 50/Sq.m.)
 - Tulipa 'Triumphator' - 20/Sq.m.

- Meadow grass seeding:**
- Grass mix with 25% Vicia sativa, 25% Leucanthemum vulgare, 25% Succisa pratensis, 25% Centaurea nigra: Application rate: 1.5g / m2/

- Manage by cutting once a year in September.**
- Leave cuttings on the ground for a couple of days to facilitate seeds dropping and then remove

- Grass seeding:**
- Grass mix (45% Amenity Ryegrass, 40% Slender Creeping Red Fescue, 10% Chewings Fescue, 5% Highland Brown top Bent): Application rate: 35g / m2/

- Planting to swales**
- Bulb species and pollinators (Allium sphaerocephalum, Dutch Crocus, Nectarosodium siculum, Camassia leichlinii 'Alba', Camassia quamash, Camassia leichlinii caerulea) planted at 10/m2/
 - Wildflower mix (Borage, Leucanthemum vulgare, Rhinanthus minor) application rate: 1.5g / m2/
 - Ornamental grass (Luzula nivea), c/f, 2L, planted at 3/m2/

Site boundary

- Existing vegetation to be retained
- Street streets level (see minimum tree table) see D-03-PP D01 for details
- Proposed Trees
- Site retention tree pits see D-03-PP and D-04-PP for details
- Proposed native woodland planting
- Proposed Myrica planting area see D-03-PP for details proposed species mix see D-03-PP D02 for details
- Proposed Native Hedge see D-03-PP D02 for details
- Proposed ornamental shrub planting
- Proposed grass
- Homezone (for engineers details and specifications) Carparking, kerbing, drainage, platform in full colour, or similar approved
- Pathways finished concrete with precast concrete kerb
- Cycle path
- Walls bonded pathway see D-04-PP D01 for details
- Walls bonded pathway with call web build up see D-04-PP D01 for details
- Paved pathways
- Bins see D-03-PP Detail D01
- Bike stands see D-03-PP Detail D02
- Timber deck sawtooth edge see D-03-PP D01 for details
- Seating see D-03-PP Detail D05
- Proposed outdoor gym equipment
- 2.0m high rendered block wall see D-03-PP D01 and D-03-PP D02 for details
- 2.0m high brick face block wall see D-03-PP D02 for details
- 2.0m high concrete and timber panel fence see D-03-PP D02 for details
- Walls 1.5m high to be retained or footer run see D-03-PP D01 for details
- Walls 1.5m high to be retained or footer run see D-03-PP D02 for details
- 2.2m high precast concrete ramp boundary to school site see D-03-PP D01 for details
- 2.0m high brickwork wall with precast concrete coping see D-03-PP D01 for details
- 100mm high stone coping see D-03-PP D01 for details
- Low wall and sitting benches from garden areas