TYPE A COLUMN DETAILS

HEIGHT	:	6m
BRACKET LENGTH	:	Post-top
INCLINATION	:	0 Degrees
COLUMN QUANTITY	:	36

LANTERN DETAILS

AVERAGE WATTAGE (CLO)	:	18w LED
MAKE & MODEL	:	C.U.Phosco P852-12-P4-NW-CB0450

TYPE B COLUMN DETAILS

HEIGHT	:	6m ABACUS Raise & lower type
BRACKET LENGTH	:	Post-top
INCLINATION	:	0 Degrees
COLUMN QUANTITY	:	2

LANTERN DETAILS

AVERAGE WATTAGE (CLO)	:	9w LED
MAKE & MODEL	:	C.U.Phosco P852-12-R3B-NW-CB0200

TYPE C COLUMN DETAILS

HEIGHT	:	6m
BRACKET LENGTH	:	Post-top
INCLINATION	:	0 Degrees
COLUMN QUANTITY	:	15

LANTERN DETAILS

AVERAGE WATTAGE (CLO)	:	25w LED
MAKE & MODEL	:	C.U.Phosco P852-12-F2-NW-CB0650

TYPE D COLUMN DETAILS

HEIGHT	:	10m
BRACKET LENGTH	:	Post-top
INCLINATION	:	0 Degrees
COLUMN QUANTITY	:	24

LANTERN DETAILS

AVERAGE WATTAGE (CLO)	:	64w LED
MAKE & MODEL	:	C.U.Phosco P862-256-P4-W5-0250

TYPE E COLUMN DETAILS

HEIGHT	:	8m
BRACKET LENGTH	:	Post-top
INCLINATION	:	0 Degrees
COLUMN QUANTITY	:	13

LANTERN DETAILS

AVERAGE WATTAGE (CLO)	:	52w LED
MAKE & MODEL	:	C.U.Phosco P862-256-P4-W5-0200

Notes:
All LED lanterns must have Constant Light Output (CLO).
Automatically dimmed to 75% each night from 12 midnight to 6am.
All lanterns to have 7pin NEMA sockets fitted.

Electronic Photocells switched at 35/18lux
All columns, luminaires, cable and pillars, shall comply with Local Authority General Specification for Public Lighting.

No trees to be located within falling distance of P/L columns.
Minimum set-back of columns is 800mm from face of kerb.

2X6iss NYCY cable laid in ducting to ETCI ET101.
Single wall ducting, colour red to be used manufactured from high density polyethylene (H.D.P.E.). 107mm external diameter, having a wall thickness of 5mm. This ducting to have the words "Street Lighting" stamped on, letter size 9mm at 1m intervals. The lettering to face uppermost in the trench. All works to Local Authority specification.
This is a circuit layout and not indicative of where ducts are to be laid.

P/L Wall Pillar

Public Lighting Pillar (located at least 2m from ESB pillar)

Public lighting cable chamber as per Local Authority P/L Dept. specification.

NOTES

THIS DRAWING IS THE INTELLECTUAL PROPERTY OF Sabre LIGHTING DESIGN DEPT. AND IS COPYWRIGHT © AND CAN NOT BE USED WITHOUT PRIOR CONSENT.

NO ACCOUNT IS TAKEN FOR THE BLOCKING EFFECT CAUSED BY BUILDINGS, TREES ETC. THE CALCULATION SHOWN BY THIS DRAWING ASSUMES THAT THE WHOLE AREA BEING CONSIDERED IS IN THE SAME PLANE, I.E. THERE ARE NO CHANGES IN GRADIENT OR ELEVATION.

This drawing layout is based on calculated lighting levels, produced by Sabre Electrical Services Ltd., using Lighting Reality software. Any alterations to the layout or luminaire type used for the lighting design calculations, will require a revised lighting design to be carried-out. A redesign may require approval from the Local Authority Public Lighting Dept. prior to any alterations/modifications being implemented on site.

Sabre
ELECTRICAL SERVICES LTD.
Specialist Contractors
PUBLIC LIGHTING - FLOOD LIGHTING - SPORTS LIGHTING

UNIT 11,
BELLVUE INDUSTRIAL ESTATE,
FINGLAS,
DUBLIN 11.
E - MAIL: graham@sabrelighting.ie PH: 01-811 0875

REV	DESCRIPTION	INITS	CHK'D	DATE
-	?	GS	CHK	----------
-	?	GS	CHK	----------
-	?	GS	CHK	----------
-	?	GS	CHK	----------
-	?	GS	CHK	----------
B	Cable chambers added to Side Street 1. MP numbers added	GS	CHK	13-01-21
A	Circuits added	GS	CHK	01-12-21

CLIENT/CUSTOMER
Quintain Ireland

PROJECT
Aderrig Phase 2

TITLE
Public Lighting Layout

DRAWN	SCALE	DATE
G.S	1:750@a1	21-05-21

DRAWING NUMBER	ISSUE
SES 07521	2

BASE DRAWING NUMBER
edit

DRAWING ORIGIN
edit

DO NOT SCALE FROM THIS DRAWING