Tree Planting Specification

Tree planting throughout the scheme has been selected to blend the development in to its surrounding environs. All trees shall comply to BS3936, Specification of Nursery Stock. The trees shall be purchased from a reputable nursery as rootball specimens and final order to be agreed by Landscape Architect; The trees shall be planted on delivery. All plant material where possible should be Irish grown Nursery Stock and the importation of foreign planting material should be avoided where possible. The planting season for bar root and rootball specimens is between the months of Nov and March. If this is not possible due to weather conditions (wet or frosty), the plants must be healed in. The tree planting shall take place no later then the first season post completion of the project. Tree root barrier shall be installed where threes are located within a 2.5m diameter from center.

Maintenance Watering is essential during the first 2 growing seasons regardless of the weather conditions - 1000Lt / Tree/ Month. Maintenance works shall be carried out in accordance with the requirements of the BS:4428 (1989) Code of practice for General Landscape Operations (excluding hard

Replacements of trees; Any trees as specified in accordance to this condition, which maybe removed, die. severely damaged or severely diseased within three years post planting shall be replaced with same or similar variety and same size as those specified below.

Specimen varieties		Specification	Size	Height	Qty
Amla	Amerlanchier lamarkii	Clearstem	14-16cm	3.5m+	13
BePe	Betulus Pendula	Clearstem	14-16cm	3,5m+	20
PiSy	Pinus Sylvestris	Clearstem	18-20cm	4.5m+	5
SoAu	Sorbus aucuparia	Clearstem	18-20cm	4.5m+	4
LiSt	Liquidamber stactiflua	Clearstem	18-20cm	4.5m+	8

Methodology and Guidance Notes: The Iree pit should have a diameter at least 100mm greater than that of the root system, with the depth not exceeding the rootball. Any glazed or smeared sides caused by digging shall be scarified with the use of a fork. The tree will be positioned in the centre of the planting pit at the correct depth, taking into account the root flare and finished level. Prior to backfilling the hessian twine/wire cage supporting the rootball shall be loosened or removed. Backfilling shall be carried out in layers of 150mm, ensuring the tree is held upright. At each stage the fill will be carefully firmed in to eliminate air pockets under and around the root system. The final layer of backfill will not be consolidated. but should be of a sufficient depth to allow for settlement and mulching. Formative pruning should be carried out if required, removing dead, damaged, crossing or diseased branches. Refer to Tree planting specification for tree achoring system. All trees planting operation will be carried in accordance with BS8545:2014 Trees: from nursery to independence in the landscape -Recommendations,

Landscape Notes:

All plant material where possible should be Irish grown Nursery Stock and the importation of foreign planting material should be avoided within the proposed planting scheme


All Landscape Works shall be undertaken by ALCI approved Landscape Contractor and in accordance with Landscape specifications. Topsoil to BS 3882:1994, general grade, free from sharp edged stone. Backfilling Materials: A previously prepared thorough mixture of:

- -70% by volume topsoil excavated for the pit and the additional topsoil as required.
- -25% by volume approved well-rotted organic material.
- -5% by volume course grained washed river sand.
- -600g/cu m bonemeal of medium fine texture, containing not so less than 20% soluble potash and 3-5% nitrogen,

Maintenance


Initial Landscape operations will be undertaken by ALCI member. All operations will be carried out to a standard specification. The contractor will be responsible for plant establishment for a three year period. Any trees and shrubs dying, damaged or removed shall be replaced in the following planting season with plant of similar size and species.


Grass Seeded Area




Sowing Rate: 30grams/sgm

Detail 2: Tree Planting Underground Guying system for Trees 18-20cm girth and over





Mixed Ornamental Planting



Dry Swale - Suggested Planting Mix

Viburnum davidii

Planted areas to be constructed for drainage perculation. Top dress planted areas with beech pebble stone 50mm+. All plant material where possible should be Irish grown Nursery Stock and the importation of foreign planting material should be avoided.

4/sam ca

5L

10%

104

Inlet planting mix	size	spacing
Iris pseudacorus (Yellow flag Iris),	2ltr	4/Sqm
Juncus effusus (Corkscrew rush)	2ltr	5/Sqm
Carex pendula (Pendulous sedge)	2ltr	5/Sqm
Lobelia cardinalis (Cardinal flower)	2ltr	4/Sqm
Zantetedeschia aethiopica (arum lily)	3ltr	2/Sqm
Lythrum salicaria (Purple loostrife).	2ltr	4/Sqm
General planting mix	size	spacing
Sambucus nigra	5ltr	1/Sqm
Cornus 'Midwinter fire'	51tr	3/Sqm
Hydrangea 'Annabelle'	5ltr	2/Sqm
Rosa rugosa	5ltr	2/Sqm
Campanula glomerata	3ltr	3/Sqm
Crocosmia 'Lucifer'	3ltr	4/Sqm
Calamagrostis brachytricha	3ltr	3/Sqm
Deschampsia cespitosa	3ltr	3/Sqm
Geranium 'Rozanne'	3ltr	3/Sqm
Hemerocallis in varieties	3ltr	4/Sqm
Iris Sibirica	3ltr	4/Sqm
Miscanthus sinensis ts layout	3ltr	3/Sqm
plant per m ² 3 plant per m ²	,	5 plant per m

¹ 2 plant per m² 4 plant per m²



Ashhourne, Co. Meath, Ph: 067 6839526 Email: jane@janemccorkell.com

The desiring is the copyright of Jane McContril Landscape & Gorden Draign has been produced to the close and project as standardore. The draining may not be repostured of an



androone appoiliantions	Dw31ef PP397-04-01			
andscape specifications	Scale	_	Sus	А3
orton Engravelend Limited	Date	JAN 2023		
Certas Energy Ireland Limited	Disamity.	SH		
put	Checked by:	JMC		
onthill Road, Liffey Valley	Rec		_	