



**Permitted Native Hedgerow** (SDCC Planning Ref. SD19A/0042)  
Native hedgerow planting to fill in gaps and establish continuity in existing native hedgerow.

**Permitted Native Hedgerow stocking rate**  
Native hedgerow planting to fill in gaps and establish continuity in existing hedgerow at a stocking rate of 3/sq.m

**Existing Hedgerow to be Retained and Strengthened.**  
Existing hedgerow to be maintained, all non-native species and dead or diseased plants to be removed. Native hedgerow species to be planted as infill to existing and to create a dense hedgerow.

**Permitted Visual Screening Belt** (SDCC Planning Ref. SD19A/0042)  
Series of earth berms creating an undulating landscape form. Combined berms to create a visual screen with triple staggered line of large native trees @ 14-16cmg, 4-5m tall on day 1 of operations to be planted on top of berm. Main tree planting with 2.5m high native conifers. Refer to planting plan (dwg 103) for detailed specifications of trees.

**Permitted Public Access Path and Seating Area.**  
Public path connecting to existing canal towpath to facilitate access to the wetland and woodland habitat areas. Access to the ponds and the wider site is controlled by 1.2m high timber post and rail fence. Two seating areas are proposed, providing views of the proposed and future ponds and wetlands.

**Permitted Pond and Wetland habitat.** (SDCC Planning Ref. SD19A/0042)  
Retention pond designed as a permanent water body including native wetland and aquatic habitats.

**Permitted Grass Tracks** (SDCC Planning Ref. SD19A/0042)  
Mown grass track providing service access routes, through landscape.

**Permitted Pond and Wetland habitat.**  
Retention pond designed as a permanent water body including native wetland and aquatic habitats.

**Permitted Attenuation Basin**

**Existing landscape to be retained**

**Existing Hedgerow to be Retained and Strengthened.**  
Existing hedgerow to be maintained, all non-native species and dead or diseased plants to be removed. Native hedgerow species to be planted as infill to existing and to create a dense hedgerow.

**Existing Native Hedgerow stocking rate**  
Native hedgerow species to be planted as infill to existing and to create a dense hedgerow at a stocking rate of 2/sq.m

**Green Wall Planting To Building Facade.**  
Tensile steel climbing support. Mix of climbing plants planted to base. Design intent is to cover full climbing frame with climbing plants.

**Permitted Visual screening belt**  
Raised earth berm and green earth retaining wall to create ridge line for tree planting at minimum of +72.00m. Triple staggered line of large native trees @ 14-16cmg, 4-5m tall on day 1 of operations to be planted on top of berm. Refer to planting plan (dwg 103) for detailed specifications of trees.

**Permitted 1.2m high post and rail fence** (SDCC Planning Ref. SD19A/0042)

**Proposed footpath linking to public circulation and access routes**  
Refer to drawing 105 for details

**Proposed alteration to permitted berms to accommodate services. Extent and height of ridge line maintained**

**Proposed Bio swale**  
Refer to drawing 104 for details

**Proposed Pond and Wetland habitat.**  
Retention pond designed as a permanent water body including native wetland and aquatic habitats.

**Proposed Bio swale**  
Refer to drawing 104 for details

**Proposed Native Hedgerow**  
New ecological corridor

**Permitted Visual Screening Belt** (SDCC Planning Ref. SD19A/0042)  
Raised earth berm to create ridge line for tree planting at +66 to +70. Triple staggered line of large native trees @ 14-16 cmg 4-5m tall on day 1 of operations to be planted on top of berm. Main tree planting supplemented with 2.5m high native conifers. Refer to planting plan (dwg 103) for detailed specifications of trees.

**Proposed Green Wall.**  
Climbing plants on tensile steel climbing support system. Refer to planting plan (dwg 103) for detailed specifications of plants

**Permitted ecological corridor**  
Proposed native hedgerow as new ecological corridor linking woodland habitats on eastern and western boundaries. Refer to planting plan (dwg 103) for detailed specifications.

**Permitted Visual Screening Belt** (SDCC Planning Ref. SD19A/0042)  
Raised earth berm to create ridge line for tree planting at +67 to +71. Triple staggered line of large native trees @ 14-16 cmg, 4-5m tall on day 1 of operations to be planted on top of berm. Main tree planting supplemented with 2.5m high native conifers. Refer to planting plan (dwg 103) for detailed specifications of trees.

**Proposed Native Hedgerow**  
New ecological corridor

**Permitted Data Centre**

**Permitted Green Wall Planting To Building Facade.**  
Tensile steel climbing support. Mix of climbing plants planted to base. Design intent is to cover full climbing frame with climbing plants.

**Permitted Visual Screening Belt**  
Raised earth berm to create ridge line for tree planting at +67 to +72. Belt of large native trees @ 14-16cmg, 4-5m tall on day 1 of operations to be planted on top of berm. Refer to planting plan (dwg 103) for detailed specifications of trees.

**Existing Hedgerow to be Retained and Strengthened.**  
Existing hedgerow to be maintained, all non-native species and dead or diseased plants to be removed. Native hedgerow species to be planted as infill to existing and to create a dense hedgerow.

**Existing Native Hedgerow stocking rate**  
Native hedgerow species to be planted as infill to existing and to create a dense hedgerow at a stocking rate of 2/sq.m

**Legend**

- Application Boundary
- Existing Trees to be Retained
- Existing Hedgerow to be Retained and Strengthened  
Existing hedgerow to be maintained, all non-native species and dead or diseased plants to be removed. Native hedgerow species to be planted as infill to existing and to create a dense hedgerow. Hedgerow will be restocked at a rate of 2/m2.
- Proposed Native Hedgerow  
Native hedgerow species to be planted in 3m wide linear band to create a dense hedgerow. New hedgerow will be planted at a rate of 3/m2
- Proposed Native Woodland  
To create a biodiverse native habitat around the perimeter and throughout the site. New planting designed to create a network of ecological corridors linking with existing vegetation to be retained. Planted as transplants with 10% of trees as 6-8 cmg, min 2m high. As the planting matures a visual screen will be created. Refer to planting schedule
- Proposed Medium or Large Deciduous Tree Planting  
To be planted at heights required to give an immediate impact and create a visual screen where required. Refer to planting schedule for specific specifications
- Proposed Native Coniferous Tree Planting  
To be planted at heights required to give an immediate impact and create a visual screen where required. To complement and strengthen the screening level provided by the large deciduous tree planting. Refer to planting schedule for specific specifications
- Proposed Street Tree Planting  
To be planted in structural tree pits. Refer to dwg no. 106, Detail D 5 no. Alnus cordata, 18-20cmg, 5.5-6m, 3m clear stem
- Proposed Formal Hedge  
Formal hedging planted in a double staggered row at 5/line m.
- Wildflower Meadow  
Area to be managed as a wildflower meadow to improve the biodiversity of the local environment and reduce maintenance operations
- Mown Grass Service Tracks
- Ornamental Planting
- Wetland Planting
- Post and Rail Fence  
1.2m high timber post and rail fence. Refer to drawing 106 for details
- Security Fence  
Refer to architects specification.
- Green Wall  
Tensile steel wire with climbing plants.

Proposed Lable Previously Permitted Lable Area modified in response to Additional information request

THIS DRAWING IS COPYRIGHT ©		Scale: 1:1000 @ A1		Status: ADDITIONAL INFORMATION	
notes: DO NOT SCALE		Date: 10/05/23		Dn: KF Cnd: KF	
figured dimensions only to be taken from this drawing		Job No: 0453		Drawing No: 201	
		4 Main Street		Kevin Fitzpatrick   Landscape Architecture	
		Raheny		E: info@kfa.ie W: www.kfa.ie	
		Dublin 5			
		E: info@kfa.ie W: www.kfa.ie			