



02 no. 2300x600x480 mm Hardwood Bench with crosswise solid slats on an integrated steel structure.



LANDSCAPE MASTER PLAN & PLANTING PLAN / scale 1:500



Acer campestre (Field Maple)



Amelanchier lamarckii (Serviceberry)



Betula pubescens (Downy Birch)



Brushed concrete paving



Natural granite aggregate paving, graphite finish. 600mm x 150mm x 80mm depth.



Exposed aggregate concrete paving

Rev/Date	Description	By
A 2017-09-05	Relocation of few trees to avoid services. Planting to ramp revised. Gravel infill to approx. 4-8mm diameter.	LP
B 2017-11-05	Site Plan amended accordingly to Amendments to the Rear of the Proposed Sports Hall as requested by the Fire Officer relating to extended footpaths from rear escape doors	LP
C 2017-12-06	New section of path at the north of PE Hall. Continuation of building perimeter path to play area. A fixed seating bench on Access path to Sports Hall Entrance included. Continuation of concrete path at entrance to GP Room. 04no. trees relocated. Root barrier included. All revisions are highlighted by revision cloud.	LP
D 2017-12-22	All product names removed.	LP

This drawing is copyright. Figured dimensions to be used in all cases. All dimensions to be checked on site prior to commencement of works.

Code	Description	Quantity
Q23/110A	PAVING - GOLDEN HARD BINDING GRAVEL	1000
Q25/150A	CONCRETE BLOCK PAVING SYSTEM	1000
Q21/115A	PAVING - IN-SITU CONCRETE, EXPOSED AGGREGATE FINISH	1000
Q21/215B	PAVING - IN-SITU CONCRETE, BRUSHED FINISH	1000
Q31/505	SEMI-MATURE NATIVE TREES	1000
Q31/200	PLANTING - PERENNIALS	1000
Q31/200	PLANTING - HERBAGEROWS	1000
Q30/310	SEEDING/TURFING - GRASS LAWNS	1000
Q50/220A	STREET FURNITURE - WOODEN SEATING	1000
Q50/220B	STREET FURNITURE - RAISED PLANTER	1000
Q50/220C	STREET FURNITURE - HARDWOOD BENCH	1000
Q23/170A	GRAVEL TRIM TO BASE OF BUILDING	1000
Q10/114A	ALUMINIUM TRIM	1000
Q10/114B	EDGING TRIM - PRESSURE-TREATED TIMBER	1000
Q10/114C	CONCRETE EDGING TO LIGHTWEIGHT PATH SYSTEM	1000
	KERB	
	TREE ROOT BARRIER	

STEPHEN DIAMOND ASSOCIATES
 CHARTERED LANDSCAPE ARCHITECTS

68 Pearse Street Dublin 2 tel: 01 6775670
 email: mail@sdca.ie fax: 01 6775669

Client Department of Education and Skills
 Project Clondalkin Adapt 18
 Title Landscape Master Plan & Planting Plan
 Drg No 16-444-TD-01 Date issued 2023-03-20 Scale 1:500 @ A1
 Drawn LP Purpose Tender Checked SD

SOFT LANDSCAPE WORKS MAINTENANCE PROGRAMME

1. Bare root transplants, hedging and rootball trees
 2. Containerised shrubs, perennials and grass lawns
 3. 12 months maintenance & delivery liability period, to commence on practical completion of soft landscape works. Planted beds, trees, hedges and transplanting 16 no. maintenance visits required per annum (April-October) carried out on a fortnightly basis and 2 additional visits one winter period. 16 no. maintenance visits required per annum.

SOFT LANDSCAPE WORKS MAINTENANCE PROGRAMME

City	Species	Height (cm)	Pod Size	Density	Container-grown (log)	Quality Specification
P1	Flowering Evergreen Perennial Mix	40-60cm	100mm	10 plants per m ²	PG	CG
P2	Perennial Mix low - medium height	40-60cm	100mm	10 plants per m ²	PG	CG
P3	Shade Tolerant Perennial Mix	40-60cm	100mm	10 plants per m ²	PG	CG
H1	Real Native Species Hedgerow in double hedgerow row	40-60cm	100mm	10 plants per m ²	PG	CG
T1	Native Woodland Mix	40-60cm	100mm	10 plants per m ²	PG	CG
T4	Woodland Scrub mix	40-60cm	100mm	10 plants per m ²	PG	CG